Serial No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.	Rs.	Rs.
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	157	0 6 0		
5	Cut stone work	C.ft.	6	2 0 0		
6	Plastering with surki mortar	Sqr.	3·98	3 8 0		
	Waste Weir at R. L. 53.00-200' long.					
1	Earthwork excavating foundation	C.yd.	160	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	900	0 4 0		
3	Burnt brick in surki mortar	,,	3,127	0 5 0		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	330	0 6 0		
5	Rough stone work for apron and revetment with the required lead, jelly wedging, etc., complete	C.yd.	220	1 12 0		
6	Plastering with surki mortar	Sqr.	19·20	3 8 0		
7	Burnt stone pin and toe slabs	S.ft.	432	0 5 0		
8	Jelly filling below apron including lead, etc.	C.yd.	83	1 0 0		
	Waste Weir Right at R. L. 53.00 200' long.					
1	Earthwork excavation foundation	C.yd.	138	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	784	0 4 0		
3	Burnt brick in surki mortar		1,920	0 5 0		
4	Burnt stone slabs 6" thick one line dressed and fixed in surki mortar	S.ft.	330	0 6 0		
5	Rough stone work for apron and revetment with the required lead, jelly backing and jelly wedging	C.yd.	153	1 12 0		
6	Plastering with surki mortar	Sqr.	5·60	3 8 0		
7	Burnt stone pin and toe slabs	S.ft.	432	0 5 0		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification dated 12th August 1938.

1. Attention of the public is drawn to the notification, calling for tenders for Constructing Town Hall at Madhugiri in pages 1415-1417, Part VI of the *Mysore Gazette*, dated 18th August 1938.

2. Tenders will be received by the Executive Engineer, Tumkur Division, up to 2 P.M. on 5th September 1938.

3. Earnest money of Rs. 575 should be credited to the Treasury and the treasury chellan enclosed.

P. RAJAGOPALAN,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 22nd August 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 26th September 1938, 4 P.M., for constructing special ward behind the Administrative Block of McGann Hospital at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury challen for Rs. 140 for having credited the earnest money to 17 (*a*) P. W. Deposits and be superscribed "Tender for constructing Special Ward behind the Administrative Block, McGann Hospital" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be, as per the sanctioned schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Tenders must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The successful tenderer will have to deposit another sum of Rs. 140 towards the security deposit before the execution of contract agreement.

Abstract estimate for constructing Special Ward in the Rear Portion of the Administrative Block of McGann Hospital, Shimoga.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Excavation for foundation	C.yd.	0 4 0	39	
2	Stone gelly concrete in surki mortar	C.ft.	0 5 0	356	
3	Size stone in lime mortar in foundations	,,	0 6 0	1,024	
4	Burnt brick in lime mortar	,,	0 4 6	1,891	
5	Burnt stone slabs 6" thick 2 line dressed	S.ft.	1 0 0	74	
6	Burnt stone bond slabs 6" thick	,,	0 10 6	155	
7	Mild steel trusses including hoisting and fixing with bed plates pointing, etc.	Cwt.	18 0 0	10.32	
8	Removing and refixing the existing set of hip trusses with necessary new accessories	,,	3 0 0	20	
9	Teak wood doors 4"×5" frames 1½" thick shutters ¼ panneled and ¾ glazed with pil headed Moracco glass with 3 pairs of approved parliamentary hinges 3" brass tower bolts at top, etc., complete	S.ft.	2 0 0	40	
10	Junglewood windows 3½"×5" frame as per existing pattern, etc., with paint, etc., complete	,,	2 4 0	63	
11	Removing the existing windows and refixing in a different place with necessary repairs and painting, etc., complete	No.	5 0 0	3	
12	Teakwood wrought and put up	C.ft.	4 0 0	5.47	
13	Removing the existing soantling teakwood wrought and put up for hips and refixing in new place	No.	0 8 0	20	
14	Roofing with 1st class Mangalore Tiles as per existing pattern with repairs, painting, etc., complete	Sqr.	35 0 0	7.10	
15	Removing old Mangalore Tiles	,,	2 0 0	2.14	
16	Do	,,	1 0 0	2.14	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
17	R.B.C. terrace with one course of brick laid edge wire with 2" cement concrete 1 : 2 : 4 all round and 2½' at top with long and cross wire rafters with 1 : 2½ cement mortar packing beneath and 3" to 6" thick brick kappi and quick lime on top and 2 courses of flat tiles laid in mortar, etc., complete	Sqr.	80 0 0	26.4	
18	Ornamental pillars 10¾' high with base caps in burnt brick in cement mortar 1 : 3 and circumference bond slabs every 3' high finished with fine lime mortar plastering and 2 coats of white washing, etc., complete	No.	20 0 0	2	
19	Plain parapet wall with burnt brick in mortar as per existing design including lime plastering and two coats of white washing	R.ft.	0 12 0	31	
20	Ornamental cornice for terrace outside all round	,,	0 6 0	31	
21	Fixing old ridge tiles in lime mortar	,,	0 4 0	52	
22	New Mangalore Ridge Tiles set in lime mortar	,,	0 12 0	20	
23	Lime mortar plastering ½"	Sqr.	3 8 0	22.01	
24	White washing 2 coats	,,	0 4 6	22.01	
25	Red colour cement skirting ½" thick cement mortar 1 : 3 plastering ⅛" colour red oxide rendering, etc., complete	,,	15 0 0	1.12	
26	Plain eave board T.W. 9"×1" with 2 coats of gray paint and fixing all round Mangalore Tiled Roof	R.ft.	0 8 0	70	
27	Providing and fixing ornamental Mangalore ridge tiles and over pendants	No.	1 8 0	3	
28	Flooring with cement 1 : 3 : 6, 1½" thick over 3" thick stone jelly in lime concrete bed finished with ½" cement mortar 1 : 3 rendering with ⅛" of red oxide colour with expansion joints, etc.	Sqr.	22 0 0	6.00	
29	Providing ornamental water spouts	Each	5 0 0	2	

P. SUBBA RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 25th July—1st September 1938.

Attention of the public is drawn to the Notification in the *Mysore Gazette*, dated 25th August 1938, Part VI, Pages 1461-1462, calling for tenders for "Constructing a Girder Bridge and forming approaches at 3 and 4–12 of Tarikere-Hosdurga Road near Ajjampur Railway Station."

The last date for receipt of Tenders will be 12th September 1938, instead of 3rd September 1938, as noted in the Notification, dated 18th August 1938.

Abstract Notification dated 1st—8th September 1938.

Attention of the public is drawn to the Notification in the *Mysore Gazette*, dated 25th August 1938, Part VI, pages 1462-1465, calling for tenders for "Constructing a Girder Bridge across Veda River in 2/16 of Sakrepatna-Banavar Road". The last date for the receipt of tenders is 12th September 1938.

C. R. IYENGAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated 19th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued, with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.